

| VEDANTA LIMITED – VALUE ADDED                    | <b>Document No:</b>   | VL/IMS/PID1/ |
|--|-----------------------|--------------|
| BUSINESS   |                       | INST/WI/01   |
| INTEGRATED MANAGEMENT SYSTEM                     | <b>Revision Date:</b> | 05/01/2022   |
| Work Instructions for Calibration & verification | Revision No:          | 09           |
| of Weighing Rins/Weigh Rridge/Weighing Tanks     | Page No ·             | 1 of 4       |

# CALIBRATION & VERIFICATION OF WEIGHING BINS/WEIGHBRIDGES /WEIGHING TANKS

**Objective**: To ensure accuracy in weighment of different components of the burden/Finished Good/Raw material.

**Scope**: This procedure is applicable for all weigh bins, Weighing tanks & weighbridges.

**Reference**: Operating manual for Sartorius make weight indicator model PR5510 & PR PR5310 and operating manual for Jihangine YH8210-B11

Standard used: 1) Calibration weights (C. I. Weights 20Kg each).

**Performance Criteria**: Accuracy in weighment as per acceptance limit +-5Kg for Weighing Bins,+-30Kg for Weigh bridge & +-20 kg for Weighing tanks

**Aspect for the Activity**: Waste generation

#### Identification of Hazards:

**Mechanical Hazard:** Impact of falling of C.I weights, Impact due to trapping of fingers under C.I Weight, Dust, Compressed Air, Vehicle collision, Hit by vehicle, Trip & Fall, Falling in Weighing Bin.

**Hazard due to Human Behaviour/Human error:** Throwing of weight from height, Alcoholism, Improper stacking of weights, not adhering to WI/ PPE, Use of non-certified crane, Fatigue.

Refer: RISK /INST/02, RISK /INST/17 & RISK/INST/21, SP/44-H, SP/44 U

**Responsibility**: Sr. Engineer Instrumentation/Associate /Inst Technician

## A) WEIGHING BIN VERIFICATION

Frequency: -Monthly Planned Shutdown.

**Procedure:** All instrument engineers should follow this procedure while verifying the weighing bins.

- 1. Inform production control room Engineer & take permission for calibrating the Bins.
- 2. Skip the Bins from batching process and apply Emergency push button at site for all the VT, VC, Scrap Belt, CB3\_11 & CB3\_21.
- 3. Put off the compressed air line valve for gates. Gate in closed position



| VEDANTA LIMITED – VALUE ADDED                    | <b>Document No:</b>   | VL/IMS/PID1/ |
|--|-----------------------|--------------|
| BUSINESS   |                       | INST/WI/01   |
| INTEGRATED MANAGEMENT SYSTEM                     | <b>Revision Date:</b> | 05/01/2022   |
| Work Instructions for Calibration & verification | <b>Revision No:</b>   | 09           |
| of Weighing Bins/Weigh Bridge/Weighing Tanks     | Page No.:             | 2 of 4       |

- 4. Ensure load cells are clear, unobstructed and in proper alignment.
- 5. All constrainers should be under proper tension. Bin should not touch any object from side, a visual gap to be ensured.
- 6. Ensure that weights are handled carefully to avoid falling on person.
- 7. The Verification of weighing Bins to be done in as it is condition without cleaning the Bins.
- 8. Load up to 30% of the calibrated span.
- 9. Load C.I weights duly certified one by one in batches of 200kgs for flux bins & 500 Kg for ore/coke bin and note down the readings in ascending order from SCADA.
- 10. Unload in batches of 200/500kgs for flux & ore/coke bin respectively & note down the readings in descending order from SCADA.
- 11. Both the Readings of PLC and weight Indicator should match, in case of deviation kindly adjust the 4-20mA.
- 12. Take signature from control room engineer and production Manager on the verification report filled for all the bins.
- 13. The error to be informed to production Head and based on the error Production dept to adjust 50% of the error quantity in books of account (receipt/Consumption) for the period of verification. This is applicable only for Coke as of now.

#### ❖ Note:

- 1. Ensure the Bins calibration are verified along with Control Room Engineer and production Manager and take the signature on the calibration report/Control Room Checklist.
- 2. In BF2 for WB1 & WB2 note the weight of Channel & plate which are used to keep the C.I weight and take this weight as Zero reference before loading the C.I weights. While filling the record the weight of Channel & plate should be mentioned in remark.

## **B) WEIGHING BIN CALIBRATION**

**Frequency**: - As and when error found in weighing Bin verification process is beyond acceptance criteria +/-5Kg.

## Procedure:

- 1. Clean the Bin Completely ensuring no material in weigh bin, remove as much as possible material stick around bin.
- 2. Ensuing the above step follow the Calibration SOP of respective indicator. Calibration to be done for 30% of span, load C.I Weight accordingly.
- 3. After the calibration is completed, Unload in batches of 200/500kgs for flux & ore/coke bin respectively & note down the readings in descending order.
- 4. Take signature form control room engineer on the calibration report filled for all the bins.



| VEDANTA LIMITED – VALUE ADDED                    | <b>Document No:</b>   | VL/IMS/PID1/ |
|--|-----------------------|--------------|
| BUSINESS   |                       | INST/WI/01   |
| INTEGRATED MANAGEMENT SYSTEM                     | <b>Revision Date:</b> | 05/01/2022   |
| Work Instructions for Calibration & verification | <b>Revision No:</b>   | 09           |
| of Weighing Bins/Weigh Bridge/Weighing Tanks     | Page No.:             | 3 of 4       |

#### ❖ Note:

- 1. Ensure the Bins calibration are calibrated along with Control Room Engineer and RHMS supervisor and take the signature on the calibration report/Control Room Checklist.
- 2. In BF2 for WB1 & WB2 note the weight of Channel & plate which are used to keep the C.I weight and add this weight during calibrating the Span.

# C) WEIGHBRIDGE CALIBRATION

Frequency: -Quarterly.

**Procedure**: All instrument engineers should follow this procedure whilst checking Calibration of the weighbridges.

- 1. Inform the concerned department (Dispatch/Raw material) in advance for calibration.
- 2. All weigh bridges to be cleaned by the weigh bridge owner before commencing the calibration activity.
- 3. Ensure load cells are clear, unobstructed and in proper alignment.
- 4. All constrainers should be under proper tension. Weigh Bridge should not touch any object from side, a visual gap to be ensured.
- 5. Calibration is to done with the help of external agency with 10 ton certified test weight.
- 6. Only certified vehicle to be used for calibrating the weigh bridge.
- 7. Calibration of weigh Bridges to be done in presence of Weigh Bridge owner.
- 8. Load Test weights duly certified one by one in batches of 1Ton & note down the readings in ascending order
- 9. Unload in batches of 1 Ton & note down the readings in descending order
- 10. In case if deviation exceeds acceptance limits (+-30Kg) inform to Weigh Bridge Owners with record and latter calibrate the weigh bridge and File the record.
- 11. File the records of Calibration/verification with signature of concerned department owner or representative assigned by owner.



| VEDANTA LIMITED – VALUE ADDED                    | <b>Document No:</b>   | VL/IMS/PID1/ |
|--|-----------------------|--------------|
| BUSINESS   |                       | INST/WI/01   |
| INTEGRATED MANAGEMENT SYSTEM                     | <b>Revision Date:</b> | 05/01/2022   |
| Work Instructions for Calibration & verification | <b>Revision No:</b>   | 09           |
| of Weighing Rins/Weigh Rridge/Weighing Tanks     | Page No ·             | 4 of 4       |

# D) WEIGHING TANK CALIBRATION

Frequency: -Quarterly.

**Procedure**: All instrument engineers should follow this procedure whilst checking Calibration of the weighing tanks.

- 1. Inform the concerned department (Operation) in advance for calibration.
- 2. Inform control room Engineer (PCI) & take permission for calibrating the weighing Tank.
- 3. Ensure load cells are clear, unobstructed and in proper alignment.
- 4. All constrainers should be under proper tension. Bin should not touch any object from side, a visual gap to be ensured.
- 5. Ensure that weights are handled carefully to avoid falling on person.
- 6. The Verification of weighing tank to be done in as it is condition.
- 7. Load up to 30% of the calibrated span.
- 8. Load C.I weights duly certified one by one in batches of 500 Kg and note down the readings in ascending order from SCADA.
- 9. Unload in batches of 500kgs respectively & note down the readings in descending order from SCADA.
- 10. Both the Readings of PLC and weight Indicator should match, in case of deviation kindly adjust the 4-20mA.
- 11. Take signature from control room engineer and production Manager on the verification report filled for all the bins.

| Prepared By:         | Reviewed & Issued By: | Approved By:         |
|----------------------|-----------------------|----------------------|
| Associate Manager–   | Management            | Head – Electrical &  |
| Electrical &         | Representative        | Instrumentation PID1 |
| Instrumentation PID1 | _                     |                      |
| Q:                   | Q!                    | Ciam of anno         |
| Signature:           | Signature:            | Signature:           |
| Signature:           | Signature:            | Signature:           |
| Signature:           | Signature:            | Signature:           |
| Date: 05/01/2022     | Date 05/01/2022       | Date 05/01/2022      |